

# SENECA COUNTY

# SUBDIVISION REGULATIONS

#### PREPARED BY:

Seneca Regional Planning Commission

71 S Washington St, Suite 1104

Tiffin, OH 44883

REVISED JUNE, 2022

the second This page intentionally left blank. -

# Table of Contents

UNIFORM SUBDIVISION REGULATIONS	4
ARTICLE I – TITLE AND PURPOSE	5
Section 100. TITLE	5
Section 101. PURPOSE	5
Section 102. FEE STRUCTURE	5
ARTICLE II – DEFINITIONS	6
Section 200. DEFINITIONS	6
ARTICLE III – SUBDIVISION PROCEDURE	10
Section 300. INITIAL PLAT INVESTIGATION	10
Section 301. PERLIMINARY PLAT REQUIRED:	10
SECTION 302 FINAL PLAT REQUIRED:	13
Section 303. MINOR SUBDIVISIONS:	16
Section 304. SUBDIVISIONS INVOLVING PRIVATE STREETS:	17
ARTICLE IV- SUBDIVISION DESIGN STANDARDS	19
SECTION 400. STREETS:	19
1. LOCATION AND ARRANGEMENT:	19
2. RIGHT-OF-WAY WIDTHS:	20
3. STREET GEOMETRICS:	20
4. STREET INTERSECTIONS	20
5. STREET JOGS:	20
Section 401. BLOCKS:	20
1. SIZES	20
2. PUBLIC WALKWAYS/BIKEWAYS:	21
3. EASEMENTS:	21
Section 402. LOTS:	21
1. SIZES AND SHAPES:	21
Section 403. NATURAL FEATURES:	22
Section 404. FLOOD AREAS AND STORM DRAIN DITCHES:	22
ARTICLE V- IMPROVEMENTS	25
Section 500. STREETS:	25
Section 501. PUBLIC UTILITIES:	25

Section 502. OTHER IMPROVEMENTS:	
ARTICLE VI – JURISDICTION	27
ARTICLE VII- INTERPRETATION/MINIMUM REQUIREMENTS	28
ARTICLE VIII – VIOLATIONS AND PENALTIES	
ARTICLE IX – SEVERABILITY	
ARTICLE X – REPEAL & AMENDMENTS	
ARTICALE XI – VARIANCE	
ARTICLE XII – APPEAL	
ARTICLE XIII – LARGE LOT DEVELOPMENTS	
SECTION 1300. Large Lot Development Rules.	
1300.01 GENERAI.	
1300.02 PRE-APPLICATION CONFERENCE AND SKETCH PLAN	
1300.03 SURVEY REQUIREMENT.	
1300.04 LOT FRONTAGE REQUIREMENT.	
1300.05 LOT WIDTH TO DEPTH RATIO.	
1300.06 APPLICATION SUBMITTAL REQUIREMENTS	
1300.07 REVIEW AND APPROVAL.	
1300.08 AGRICULTURAL AND PERSONAL RECREATIONAL PURPOSES EXEMPTION	
ARTICLE XIV – ENACTMENT	
Section 1400. EFFECTIVE DATE	
APPENDIX	40
APPENDIX	

# UNIFORM SUBDIVISION REGULATIONS

For the subdivision and improvement of land with the jurisdiction of the Board of Seneca County Commissioners and the Seneca Regional Planning Commission, Seneca County, Ohio, in accordance with Chapter 711 of the Ohio Revised Code.

The Seneca County Subdivision Regulations were initially enacted by the Seneca County Commissioners on October 5, 1995. The Seneca County Commissioners and Seneca Regional Planning Commission adopted amended regulations on:

- November 17, 1997
- December 26, 2002
- February 9, 2006.

MAL

This current version fo the Seneca County Subdivision Regulations were Accepted and adopted by the Board of Seneca County Commissioners on August \_\_\_\_\_, 2022.

These regulations were adopted by the Seneca Regional Planning Commission on August \_\_\_\_\_\_, 2022 and became effective on September 1, 2022.

The purpose of the Seneca County Subdivision Regulations are to protect the public health, safety, comfort, convenience and general welfare; and regulating the development of the subdivided areas; promoting the proper arrangement of street and layout of lots; providing the adequate and convenient provision of open spaces, utilities, recreation and provision of water, drainage, sewer and other sanitary facilities; providing for the administration of these regulations and defining the powers and duties of the administrative officers; prescribing penalties for the violation of the provisions of the resolution of any amendments thereto; and for the repeal thereof.

# ARTICLE I – TITLE AND PURPOSE

#### Section 100. TITLE

These Regulations shall be known and may be cited and referred to as the Subdivision Regulations of Seneca County, Ohio: and shall hereafter be referred to as these regulations.

### Section 101. PURPOSE

The purposes of these regulations are to provide for the orderly growth and harmonious development of the County; to secure adequate traffic circulation through the coordinated street systems with relation to major thoroughfares, adjoining subdivisions, and public facilities; to achieve individual property lots of maximum utility and livability; to secure adequate provisions for water supply, drainage, and sanitary sewage disposal, and other health requirements, and to provide logical procedures for the achievement of the purposes.

### Section 102. FEE STRUCTURE

Fee shall be established by the Seneca Regional Planning Commission.

Major Subdivisions will have the following Fee Structure:

*Plan Approvals	\$200.00
*Administration Fee	\$250.00
*Application Fee (Up to 2 Hours of Review)	\$300.00
*Application Fee (Beyond 2 Hours of Review)	\$150.00 Per Hour

\*The Plan Approval, Administration, and Initial Application fee shall be paid at the time the application is submitted.

\*\*Applicants will be responsible for all advertising fees and will be invoiced accordingly.

Minor Subdivision will have the following Fee Structure:

	*A minor lot split	\$40.00
NY.	* 2 <sup>nd</sup> , 3 <sup>rd</sup> , or 4 <sup>th</sup> <i>from the same tract</i> after the first	\$10.00 each
ζ.	*Processing/Administration fee for non-member townships (Payable by the applicant)	\$150.00

# ARTICLE II – DEFINITIONS

### Section 200. DEFINITIONS

The following definitions shall apply in the interpretation and enforcement of these regulations:

Accessory Building: A building on the same lot with, and incidental and subordinate to, the principal building.

Alley: A dedicated public way affording a secondary means of access to abutting property and no intended for general traffic circulation.

**Block:** That property abutting one side of a street and lying between the two nearest intersecting streets, or between the nearest such street and railroad right-of-way, unsubdivided acreage, river of live stream; or between any of the foregoing and any other barrier to the continuity of development.

**Board:** The Seneca Regional Planning Commission.

**Comprehensive Plan:** Any plan, or portion thereof, adopted by the Seneca Regional Planning Commission and the Board of the Seneca County Commissioners which may include the general location and extent of the present and proposed physical facilities, including housing, industrial and commercial uses, major streets, parks, school, and other community facilities. This plan establishes the goals, objectives, and policies of the community.

**Drawings:** For the purpose of these regulations, a printed, computer-generated plat representing a Minor, Major or Large Lot Subdivision that is submitted for final review and approval under these regulations.

**Dwelling Unit:** A building or portion thereof designed for human occupancy for residential purposes.

**Easement:** Specific area of land over which a liberty, privilege, or advantage is granted by the owner to the public, a corporation, or some particular person or part of the public for specific uses and purposes, and which shall be designated a public or private easement, depending upon the nature of the user.

**Engineer, Professional**: Any person registered to practice professional engineering by the Ohio State Board of Registration as specified in Section 4733.14 Ohio Revised Code.

**Flag Lot:** A lot so shaped that the majority of the lot area is connected to a public roadway by a minimum, constant width of land. A typical flag lot configuration is one that resembles a flag and pole or a pan and handle. Lot size and dimensions shall exclude the pole portion of the lot.

**Improvements:** Street pavement of resurfacing, curbs, gutters, sidewalks, water lines, sewer lines, storm drains, streetlights, flood control and drainage facilities, utility loves, landscaping, and other related matters normally associated with the development of land into building sites.

Lot: For purposes of these regulations, a lot is a parcel of land equal to or less than 5 acres, coverage, and area, and to provide such yards and other open spaces as are herein required. Such lot shall have a minimum frontage on an improved public street, of on an approved private street, and may consist of:

- A. A Single lot of record;
- B. A Portion of a lot of record;
- C. One of more complete lots of record, compete lots of record and portions of lots of record, or portions of lots of record.

**Major Thoroughfare Plan:** The part of the Comprehensive Land Use Plan which may include the location, alignment and dimensions of existing and proposed streets and thoroughfares.

**Minor Subdivision:** A division of a parcel of land that does not require a plat to be approved by a planning authority according to Section 711.131, Ohio Revised Code.

**Performance Bond or Surety Bond:** A guarantee by a subdivider or developer to the Board of Seneca County Commissioners, or their designated agent, in the amount of the construction cost, as completed by the professional engineer, assuring the completion of certain physical improvements according to approved plans and specifications, and within the time prescribed by the subdivider's guarantee. Said bond must remain in effect for a minimum of two years after final plat approval.

Plat: A map of a Subdivision of land;

1. Preliminary Plat: A map showing all requisite details of a proposed subdivision submitted to the Board for purposes of preliminary consideration, prepared in conformance with the requirements of these regulations.

2. Final Plat: A map of all or part of a subdivision providing substantial conformance to the preliminary plat of the subdivision, prepared in conformance with the requirements of these regulations and suitable for recording by the Seneca County Recorder.

**Public utility:** Any individual, firm, association, syndicate, corporation, partnership, municipal department, Commission or Board, duly authorized to furnish, and furnished under governmental regulations, to the public: facilities, products, or services such as gas, electricity, sewage disposal, communication, transportation, water, etc.

**Public Walkway/Bikeway:** A right-of-way dedicated for the purpose of pedestrian/bicycle access through residential areas, and located so as to connect to two or more streets, of a street and a public land parcel.

**Setback Line:** A line established by these regulations and/or zoning resolution, generally parallel with and measured from the front street right of way, defining the limits of a yard in which no building, other than accessory buildings, or structures may be located about ground.

**Street:** Any street, avenue, boulevard, road, lane, parkway, viaduct, or other way which is an existing federal, state, county, township, or municipal roadway; or a street or way shown in a plat heretofore approved pursuant to law or approved by official action; or a street or way on a plat duly files and recorded in the office of the Seneca County Recorder. A street includes the land between the right-of-way lines, whether improved or unimproved, and may comprise pavement, shoulders, gutters, sidewalks parking areas and lawns.

- 1. Major Thoroughfare: An arterial street of extended continuity which is intended to serve as a large volume traffic-way for both the immediate area and region beyond, and which are designated as such on the Comprehensive Land Use Plan.
- 2. Secondary Thoroughfare: A street primarily used to carry traffic from minor streets to major thoroughfare: A street primarily used to carry traffic from minor streets to major thoroughfares. Such streets are designated as such on the Comprehensive Land Use Plan.
- 3. Minor Streets: A street of limited continuity used primarily for access to abutting properties.
- 4. Marginal Access Street: A minor street paralleling and adjacent to a major thoroughfare that provided access to a abutting properties and protection from though traffic.
- 5. Boulevard Street: A street developed to two, one-way pavements, separated by a median.
- 6. Turn-Around: A short boulevard street permanently terminated by a vehicular turnaround.
- 7. Cul-De-Sac Street: A minor street of short length, having one end open to traffic and being permanently terminated at the other end by a vehicular turn-around.

**Street Jog:** Two (2) separated intersects from one (1) road to another, one (1) or more of which are stop controlled.

**Subdivider:** Any individual, firm, association, syndicate, partnership, corporation, trust, or any other legal entity commencing proceedings under these regulations to affect a subdivision of land hereunder for itself or for another.

#### Subdivision:

- 1. The division of any parcel of land shown as a unit or as a contiguous units on the tax roll next proceeding October 5,1995, that date of adoption of Seneca County's original Subdivision Regulations, into two (2) or more parcels, sites, or a lot, at least one of which is five (5) acres or less in area.
- 2. Partition of land into parcels of more than five (5) acres not involving any new streets or easements or access
- 3. The sale or exchange of parcels between adjoining lot owners, where such sale or exchange does not create additional building sites. Said subdivisions shall be exempt from regulations, subject to the following requirements: grantor lot serviced by public sewer remain larger than nine thousand six hundred (9600) square feet, grantor lot serviced by on lot septic remain larger than one (1) acre or subject to appropriate zoning.
- 4. The improvement of one or more parcels of land for residential, commercial, or industrial structures or groups of structures involving the division or allocation of land for the opening, widening or extension of any street or streets, except private streets serving industrial structures; the division or allocation of land as open space for common use by owners, occupants, or lease holders, or as easements for the extension and maintenance of public sewer, water, storm drainage or other public facilities. (See Minor Subdivision)

**Surveyor, Professional:** Any person registered to practice surveying by the Ohio State Board of Registration as specified in Section 4733.14 Ohio Revised Code.

**Variance:** A variance is a modification of the strict terms of the relevant regulations where such modification will not be contrary to the public interest, and where owing to conditions peculiar to the property and not the result of the action of the applicant, a literal enforcement of the regulations would result in unnecessary and undue hardship on the land.

Vicinity Map: A drawing located on the plat which sets forth by dimensions or other means, the relationship of the proposed subdivision or use to other nearby developments, landmarks, community facilities and services, and/or watersheds within and adjacent to Seneca County in order to better locate the area in question.

9 | Page

# ARTICLE III – SUBDIVISION PROCEDURE

### Section 300. INITIAL PLAT INVESTIGATION

The Subdivider shall meet with the Regional Planning Commission or its designated representative prior to submitting the preliminary plat. The purpose of this meeting is to discuss early and informally the purpose and effect of these Regulations and the criteria and standards contained therein; and to attempt to familiarize the Subdivider with the laws, regulations and plans as exemplified by the Comprehensive Land Use Plan, applicable zoning standards, and the drainage, sewerages, and water systems for the County of Seneca and the State of Ohio.

### Section 301. PERLIMINARY PLAT REQUIRED

After the initial plat investigation, the Subdivider shall submit a preliminary plat of the proposed subdivision, which shall conform to the requirements set forth in this Section, see Attachment A for Application. A professional Surveyor and/or a Professional Engineer shall prepare the Preliminary Plat

The Procedure for preparation and submittal of a preliminary plat of the land area to be subdivided shall be as follows:

#### 1. Filing:

A. A minimum of five (5) copies of the preliminary plat of the proposed subdivision, include a pdf electronic copy, together with a written application, shall be sent to the following for review:

- I. Seneca Regional Planning Commission
- II. Seneca County Engineer
- III. Township Trustees & Zoning (if applicable)
  - City\Village (if applicable)
  - Seneca Conservation District
- VI. Developer
- VII. Seneca County General Health District
- VIII. Utilities (Cable, Gas, Water, Electric, Phone, Etc.)
- IX. Fire Department
- X. School Board
- XI. Flood Plain Manager
- The remaining copies shall be filed with Regional Planning

B. Submittal with the Commission shall be at least 45 days prior to the First
Wednesday of the even month which meeting shall be considered the date of filing, at which the Subdivider or his agent will be scheduled to appear.
Should any of the data in this Section 301 be omitted, the Board Staff shall

notify the Subdivider of the additional data required and Board action shall be delayed until the required data is received. The meeting date of the Board after receipt of the required data shall be the date of filing. The Board shall act on the preliminary plat at the next regular board meeting following said filing.

#### 2. Identification and Description: The preliminary plat shall include:

- A. Proposed name of subdivision
- B. Location by Township, Section, or other legal description
- C. Names and addresses of; the Subdivider, owner, planner, designer, Professional Surveyor and Professional Engineer who designed the subdivision layout. The Subdivider shall also indicate his interest in the land.
- D. Scale of plat, 1" = 100' as minimum acceptable scale, and shall be presented on one or more sheets of 24" by 36" in size.
- E. Date and North Point

#### 3. Existing Conditions: The preliminary plat shall include:

- A. A vicinity map at a scale of minimum to  $1^{"} = 1$  mile maximum shall be provided showing the relationship of the subdivision to its surroundings with one-half (1/2) mile.
- B. Boundary line of the proposed subdivision, section or corporation lines within or adjacent to the tract, and overall property dimensions.
- C. Names of all adjacent subdivisions, owners of adjoin parcels of unsubdivided land, and the location of their boundary lines.
- D. Location, widths and names of existing or prior platted streets and public easements within or adjacent to the tract being proposed for subdivisions, including those located across abutting roads. The location, width and names of existing streets, railroad right of way, easements, parks, permanent buildings, and corporation and township lines.
- E. Location of existing sewers water mains, storm drains and other underground facilities within and adjacent to the tract being proposed for subdivision.
- F. Topography drawn as contours with a consistent interval of less than or equal to two (2) feet. Topography is to be based on U.S.G.S. datum. The location of wooded areas and other significant topographic and natural features within and adjacent to the plat for a minimum of 200 feet.
- G. Existing Zoning.
- H. Soils information: including, soil type, wetlands, and flood plain locations as defined on the most current FEMA maps.
- I. List of interested partied on application and contact information for said party(s) as an attachment to the application.

11 | Page

#### 4. Proposed Conditions: The preliminary plat shall include:

- A. Layout of streets indicating proposed street, number(s), obtained from the Seneca County Engineer, right-of-way widths, and connections with adjoining platted streets, and also the widths and location of easements and public walkways/bikeways.
- B. Layout, numbers, and approximate dimensions of lots, including building setback lines showing dimensions.
- C. Indication of parcels of land intended to be dedicated or set aside for public use or for the use of property owners in the subdivision.
- D. An indication of ownership of or interest in adjacent parcels and the subdivider's future development interest. In the case where the Subdivider wishes to subdivide a given area but wishes to begin with only a portion of the total area, the preliminary plat shall include the proposed general layout for the entire area. The part, which is proposed to be subdivided, first shall be clearly superimposed upon the overall plan in order to illustrate clearly the method of development, which the Subdivider intends to follow. Each subsequent plat shall follow the same procedure until the entire area controlled by the Subdivider is subdivided. The approvals of a portion of a subdivision DOES NOT under any circumstances include future development interest within the subdivision. Future plans may have additional/less requirements due to the changes in laws and/or specifications.
- E. A written recommendation of the proposed systems for water supply, sewage disposal, storm drainage and control of soil erosion and sedimentation according to standards established by the Ohio EPA, National Pollution Discharge Elimination System (NPDES), Seneca County General Health District, the Board of County Commissioners, the County Engineer, Seneca SWCD, and Seneca County Sewer District.
- F. Statement of proposed use of lots, giving the type and number of dwelling units, existing and proposed zoning (if applicable), setbacks and type of business of industry.

**G.** Location and approximate dimensions of all existing buildings.

H. For commercial and industrial development, the location, dimensions, and approximate grade of proposed parking and loading areas, alleys, pedestrian walks, streets and the points of vehicular ingress and egress to the

- development.
- I. Descriptions of proposed covenants and restrictions.
- J. Existing and proposed final grades.

#### 5. Preliminary Plat Review by Planning Board:

- A. The regional Planning Commission staff shall within thirty (30) days, review and check for completeness of the preliminary plat as submitted. When complete and basically in conformance with Seneca County Subdivision Regulations, the preliminary plat can be placed on the agenda of the next regular Board meeting.
- B. The staff shall assemble all comments from the agencies that receive preliminary plats and shall transmit all comments to the Planning Commission.
- C. The Board shall review all details of the proposed subdivision within the framework of applicable zoning regulations, within the various elements of the Comprehensive Land Use Plan, and within the standards of these Regulations.
- D. The Board shall 1) approve 2) approve with condition(s) 3) disapprove the preliminary plat.
  - (1) Should be Board disapprove the preliminary plat, it shall record the reasons in the minutes of the meeting. A copy of the minutes shall be sent to the Subdivider.
  - (2) Should the Board find that all conditions have been satisfactorily met; it may give approval to the preliminary plat. On approval, the President shall sign to that effect on the preliminary plat and copies of the front sheets shall be distributed as follows.
    - (a) Return one the original to the Subdivider
    - (b) Retain one Copy, which shall become a matter of record in the Board Files
    - (c) Forward one copy, which shall become a matter of record in the Board files
    - (d) Forward one copy to the Seneca County Engineer
    - (e) Forward one copy to the Township Trustees
    - (f) Forward one copy to the Seneca County Auditor
    - (g) All Parties are to receive a digital copy.

Copies of the meeting minutes shall be sent to those parties of interest from Section 301 (1) A of these Regulations.

#### 6. Approval Period:

The approval of the preliminary plat shall be effective for a maximum period of twelve (12) months and shall guarantee that the terms under which the approval was granted will now be affected by changes to these Regulations during that period. The Board may grant one (1) extension not to exceed 12 months after a written request from the owner is delivered to the Planning Commission.

# Section 302 Final Plat Required:

The Subdivider, having received approval of the preliminary plat, shall submit a final plat of the subdivision within the period established in Section 301 (6) of these Regulations, and drawings

and specifications of the improvements required therein. The final plat shall have incorporated all changes in the preliminary plat required by the Regional Planning Commission. It shall conform to the preliminary plat. The final plat shall bear the date, seal, and signature of a Professional Surveyor and the supplementary information shall bear the date, seal, and signature of a Professional Engineer Licensed in the State of Ohio.

- 1. Preparation
  - a. Final Plat Form: The final plat shall be legibly drawn in waterproof archival or permanent ink on bond stock or other material of equal permanence. It shall be drawn at a scale not less than on hundred (100) feet to the inch and shall be one or more sheets 24' X 36' in size. If more than one sheet is needed, each sheet shall be numbered and relation of one sheet to another clearly shown. The signatures of all approval authorities shall be in waterproof, permanent ink. Include one set original signatures, the rest may be electronic.
  - b. Final Review: All final plats must be reviewed, approved, and signed by the Seneca County General Health District, Seneca Conservation District, Sanitary Engineer, County Engineer, Township zoning if appropriate, and County Commissioners, prior to being signed by the President of the Seneca Regional Planning Commission and filed with the Seneca County Recorder. The Subdivider shall provide an appropriate space on the final plat for all agencies to certify its approval thereof.
  - c. Regulations Governing Improvements: The final plat drawings and specifications shall include a set of construction and utility plans, including typical sections, plans and profile views, construction details and estimates of quantities. All typical sections, major engineering details, and construction estimate (submitted by a professional engineer) that are to be used on any particular public improvement shall be approved in advanced by the County Engineer before completion of the plans. Before surety is accepted, it shall be approved by the Seneca County Commissioners. Prior to the granting of approval of the final plat, the Subdivider shall have installed the minimum required improvements, or shall have furnished a surety or certified check for the amount of the estimated construction cost of the ultimate installation and initial maintenance of the improvements. Surety is to be retained for 10 years by the Seneca County Commissioners Office.
  - d. Final Plat Contents: The final plat shall contain the following information:
    - (1) Name of the subdivision, location by township and section, date, north point, scale, and acreage; acreage shall be indicated by Section and/or Corporation boundaries.
    - (2) Name and address of the Subdivider, and the Professional Surveyor who prepared the plat and appropriate registration number, seal, signature, and date.
    - (3) Plat boundaries, based on accurate traverse, with angular and lineal dimensions. All dimensions, both linear and angular, shall be



determined by an accurate control survey in the field which must balance and close within the minimum standards of *Boundary Surveys in the State of Oho*, ORC 4733.37 ORC, or modifications as established by the Seneca County Engineer/Seneca county Auditor or city Engineer, or whichever is more restrictive. All locations of monument and pins shall be as defined in Section 4733.37.03 ORC, Monumentation.

- (4) Bearings and distances to the nearest established township section corner and reference the nearest street lines or other recognized permanent monuments.
- (5) Exact locations, right-of-way, all street numbers, (obtained from the Seneca County Engineer), and house numbers, (obtained from the County Auditor) within and adjoining the plat and building setback lines.
- (6) Radii, internal angles, points of curvature, tangent bearings, lengths of arcs, and lengths and bearings of chords of all applicable streets within the plat area.
- (7) All easements and rights-of-way provided for public services or utilities.
- (8) All lot numbers and lines with accurate dimensions in feet and hundredths. When lots are located on a curve, the lot width at the building setback line shall be shown.
- (9) Accurate outlines of any area to be reserved for the common use of all property owners. Drainage and other utility easements the proposed use, maintenance responsibility, and accurate locations shall be shown for each parcel of land to be dedicated.
- A copy of any restrictions and covenants the Subdivider intends to include in the deeds to the lots in the subdivision. NOTE: Enforcement of restrictions and/or covenants shall not be the responsibility of governmental agencies.

11) Certification by a Professional Surveyor to the effect that the plat represents a survey made by that surveyor and that the monuments shown thereon exist as located and that all dimensional details are correct.

(12) Notarized certification by the owner or owners of the adoption of the plat and dedication of streets and other public areas.

(13) Typical sections and complete profiles of streets, sanitary sewers, storm water sewers, other related improvements to be constructed in the proposed subdivision, and written approval of all construction plans by the appropriate agency shall accompany the final plat.

- (14) Final plat shall only show area approved and not proposed future development.
- 2. Final Plat Review:
- A. Application for Approval of Final Plat: An application for approval for the final plat shall be submitted in writing to the Regional Planning Commission on forms provided by the Commission, see Attachment B, together with seven (5) copies of the plat, the original, and any supplementary information specified.
  - a. This material shall be submitted at least ten (10) days prior to the date of any regular Board meeting, which date shall be considered the date of filing.
- B. Approval of the Final plat: (all signatures must be obtained before the final approval) The Regional Planning Commission shall approve, disapprove, or approve with conditions (said conditions must be met within a stated period of the time) the final plat after it has been filed. If the plat is disapproved, the grounds for disapproval shall be stated in the records of the Board and copy of said record will be forwarded to the owners/subdivider. If disapproved, the Subdivider may make the necessary corrections and submit the final plat to the Board for its reconsideration. When the Regional Planning Commission has approved the final plat, the original tracing shall be returned to the Subdivider for filing with the County Recorder after all necessary certifications are received.

### Section 303. MINOR SUBDIVISIONS

Approval without a plat of a minor subdivision may be granted by the Seneca Regional Planning Commission through review by the Minor Subdivision/Lot Split subcommittee weekly review subject to the following conditions:

- 1. The proposed minor subdivision is located along an existing public road and involves no opening, widening, or extension of any street or road;
- 2. No more than five (5) lots are involved after the original parcel has been completely subdivided;
- 3. The property split application has been completed (see Attachment C) and appropriate fee has been paid.
- 4. The proposed minor subdivision has received written approval of the Seneca County General Health District and/or the Seneca County Sewer District relative to Subdivision Regulations of the County of Seneca, Ohio method of sewage disposal.
- 5. The proposed minor subdivision has received written approval of the Seneca County Engineer, Flood Plain Coordinator, and the Seneca Conservation District.
- 6. The proposed minor subdivision has access point approved by permit by the regulating subdivision. All approvals will expire if transfer does not occur within twelve months.
- See Attachment D for procedure for placing minor subdivision titles under maintenance.
  7. The proposed minor subdivision is not contrary to applicable minor subdivision design standards or township zoning regulations if such exist. If no regulations exist, landowner

must own a minimum of 35-foot contiguous frontage per lot to an existing public street. \*\*If under 5 acres.

- 8. All lots abutting a Major Thoroughfare as defined in Section 200 of these Regulations shall bear a side lot or rear lot relationship to such Thoroughfare, or be provided with a marginal access drive if a front lot relationship is unavoidable; does not access major road
- 9. The property has been surveyed by a Professional Surveyor and a boundary survey and legal description, as defined in Section 4733 ORC, Seneca County Conveyance Standards of the property is submitted with the application for approval.

If approval is requested under these provisions, and if the proposed minor subdivision is in compliance with items 1 through 7 above, upon presentation of a conveyance of said parcel, an authorized representative of the Seneca Regional Planning Commission shall certify Approval by the Seneca Regional Planning Commission; no plat required, and the authorized representative of the Board shall sign to approve the conveyance. The approved survey must be filed at the Tax Map Office accompanied by a new deed, survey, legal description, and approved lot split application form. (Attachment C)

### Section 304. SUBDIVISIONS INVOLVING PRIVATE STREETS:

Subdivisions employing private streets as a means of access to individual lots may be permitted, subject to the following conditions:

- 1. The private street shall be located within a roadway easement having a width of not less than six (60) feet.
- 2. All lots shall have a minimum area of five (5) acres, exclusive of the roadway easement, or any public street right-of-way; provided, that if a local zoning regulations permit, density may be increased to one (1) dwelling unit per acre if the subdivisions is to be served by a centralized sewage treatment system. Unless otherwise permitted by local zoning regulations, all dwellings in subdivisions served by private streets shall be single-family residential structures. Unless otherwise prohibited by local zoning regulations, condominium projects having no more than six (6) dwelling units per acre shall be permitted provided that all applicable sanitary and storm water discharge regulations are met.
- 3. The plat shall be accompanied by restrictive covenants, which prohibit further division of the lots unless the private street is improved to Seneca County standards, the street right-of way is dedicated, and the street is accepted for public maintenance.

4. A maintenance agreement must be filed with restrictive covenants to detail private roadway maintenance and repair.

Subdivisions using private streets shall be reviewed in the same manner as any other record subdivision and shall be subject to design standards presented in Article IV.



# ARTICLE IV- SUBDIVISION DESIGN STANDARDS

The regulations of this Article shall control the manner in which streets, lots, and other elements of subdivision are arranged on the land. These design controls shall help insure convenient and safe streets, creation of usable lots, provision of space for public utilities, and reservation of land for recreational uses. The planning of attractive and functional neighborhoods shall be prompted, minimizing the undesirable feature of unplanned, haphazard growth.

### **SECTION 400. STREETS:**

Street(s) in proposed subdivisions shall conform to at least the following minimum requirements:

#### 1. Location and Arrangement:

- a. The proposed subdivision shall conform to the various elements of the Seneca County Comprehensive Land Use Plan and shall be considered in the relation to the existing and planned Major and Secondary Thoroughfares, and such streets shall be platted in the location and width indicated on such Plan.
- b. The street layout shall provide for continuation of Secondary Thoroughfares and minor streets in adjoining subdivisions or the proper projection of streets when adjoining property is not subdivided.
- c. The street layout shall include minor streets so laid out that their use by through traffic shall be discouraged.
- d. Should a proposed subdivision border on or contain an existing or proposed Major thoroughfare, the Board may require marginal access streets, reverse frontage, or such other treatment as may be necessary for adequate protection of residential properties and to afford separation of traffic and reduction of traffic hazards.
- e. Should a proposed subdivision border on or contain a railroad, expressway, or other limited access highway right-of-way, the Board may require the location of a street for the development of the intervening land. Such distances shall be determined with due consideration of the minimum distance required for approach grades to future grade separation.
- f. Half width streets shall be prohibited.
- g. Permanent dead-end streets shall not be permitted. Temporary dead-end streets shall be permitted only as part of a continuing street plan, and only if a turn-around satisfactory to the Board in design is provided and provisions for maintenance and removal are advanced.

2. Right-of-Way Widths: Street right-of-way widths shall conform to at least the following minimum requirements:

#### <u>STREET TYPE</u>

- a. Major Thoroughfare (**divided**)
- b. Secondary Thoroughfare (undivided)
- c. Industrial Service Streets
- d. Multiple-family residential Streets (where platted)
- e. Minor (single family Residential) streets
- f. f. Cul-de-sac Streets
- g. Turn-Arounds
  - a) Industrial
  - b) Residential & Others

80'-120'
60' with curb and gutter
50' with curb and gutter
50' with curb and gutter

**RIGHT-OF-WAY WIDTHS** 

120' 80'

70' Radius 60' Radius (50' paved)

- i. Length for cul-de-sac streets shall not exceed 1400 feet.
- j. Length for marginal access streets shall not exceed 400 feet.
- **3. Street Geometrics:** Standards for maximum and minimum street grades, vertical and horizontal street curves and sight distances shall be established by the Construction Code for the Subdivision Regulations of Seneca County.
- **4. Street Intersections:** Streets shall be laid out so as to intersect as nearly as possible to ninety (90) degrees. Curved streets intersecting with Major Thoroughfares and Secondary Thoroughfares shall do so with a tangent section of centerline not less than fifty (50) feet in length, measured from the right-of-way line of the Major Secondary Thoroughfare.
- **5. Street Jogs:** Street jogs with centerline offsets of less than one hundred twenty-five (125) feet shall be prohibited.

# Section 401. BLOCKS:

Blocks within major subdivisions shall conform to the following standards:

### 1. Sizes

Blocks shall not exceed one thousand, four hundred (1,400) feet in length, except where, in the opinion of the Board, conditions may justify a greater distance.

b. Widths of blocks shall be determined by the condition of the layout and shall be suited to the intended layout.



#### 2. Public Walkways/Bikeways:

- a. Location of public walkways/bikeways or crosswalks may be required by the Board to obtain satisfactory pedestrian access to public or private facilities, or where blocks exceed nine hundred (900) feet in length.
- b. Public Walkways/bikeways shall be in the nature of an easement for this purpose or the purpose of a public right of way.

#### 3. Easements:

- a. Location of utility line easements shall be provided along the rear or front and side lot lines as necessary for utility lines. Easements shall give access to every lot, park or public grounds. Such easements shall be a total of not less than twenty (20) feet wide, ten (10) feet from each parcel; front easements may be ten (10) feet wide.
- b. Recommendations of the proposed layout and easement requirements of telephone, electric, and water lines shall be sought by the subdivider from all of the utility companies serving the area.

#### Section 402. LOTS:

Lots within major subdivisions shall conform to the following standards:

#### 1. Sizes and Shapes:

- a. The size, width, depth, and shape of any lot in the proposed subdivision shall be appropriate for the location and the type of development contemplated. When a subdivision in an area not regulated by local zoning is to be connected to public water and sanitary sewer facilities or to a community sewage disposal plant, and when lots in such subdivision are intended for single-family residential use, all lots shall have a minimum width of seventy-five (75) feet at the required building setback line and a minimum area of nine thousand (9,000) square feet. In areas where Township zoning regulations are in effect, the lot width and lot area requirements of such zoning regulations shall control where more restrictive.
- b. Whenever either public or community sewage disposal facilities are not available, lots intended for single-family residential use shall have a minimum width of one hundred twenty-five (125) feet and a minimum area of one (1) acre excluding right of way and/or easements(s), and conform to standards of the Seneca County Department of Health.

Unless otherwise controlled by township zoning regulations, the minimum front yard setback shall be thirty (30) feet, side yard ten (10) feet and rear yard thirty (30) feet. In the case of a rear yard abutting a side yard, the side yard setback shall be not less than the minimum front yard setback required herein, and all regulations applicable to a front yard shall apply.

- d. Corner lots in residential subdivisions shall platted at least ten (10) feet wider than the minimum width permitted by these regulations or any applicable zoning regulations.
- e. Excessive lot depth in relation to width should be avoided. A depth-to-width ratio of 3 to 1 shall be considered a maximum, unless over 5 acres then 4 to 1 with 60 foot frontage. Exemptions may be granted due to natural barriers.
- f. Lots intended for purposes other than residential use shall be specifically designed for such purposes, and shall have adequate provision for off-street parking, setbacks, and loading and unloading areas.
- g. Lots may not be created by dividing land at the ends of stub streets in adjacent subdivisions, such stub streets being intended to provide continuity of street systems in adjoining subdivisions.
- h. All parcels 20 acres or less shall be provided not less than sixty (60) feet of frontage on a public roadway, or on a private roadway that has been approved as part of a record subdivision plat. All lot splits 20 acres or less must have a minimum 35' of frontage at a location suitable for parcel access or replace with a flag parcel.

#### 2. Arrangement:

- a. Every lot shall front or abut a public street or approved private street, except lots that have existed prior to the effective date of these Regulations, and which are so recorded in the records of Seneca County, may remain.
- b. Wherever practical, side lot lines shall be at right angles or radial to the street rightof-way lines.
- c. Residential lots abutting Major Thoroughfares, where marginal access streets are not desirable or possible to attain, shall be platted with reverse frontage lots, or with side lot lines parallel to the major traffic streets. This requirement may be waived by mutual consent of the Planning Board and the County Engineer.
- d. Lots should have a front-to-front relationship across all streets where possible.

# Section 403. NATURAL FEATURES:

To the greatest extent possible, the natural drainage features and character of land must be preserved. The preservation of drainage and natural stream channels must be considered by the Subdivider and dedication and provision of adequate barriers and erosion control structures

Where appropriate, shall be required.

### Section 404. FLOOD AREAS AND STORM DRAIN DITCHES: 1. Flood Plan Areas:

All subdivisions shall conform to the Seneca County Federal Emergency Management Agency (FEMA) Flood Plain Regulations and pursuant to Ohio Revised Code Chapters 307.37 and 306.85 and any amendments thereto. Such Regulations are available through FEMA. Whenever all or part of a proposed subdivision lies within an Area of Special Flood Hazard as identified in the most recent available mapping published by the Federal Emergency Management Agency (FEMA, approval of the subdivision plat shall be conditioned on the following:

- A. No encroachment by either fill material or future structures shall be permitted in the area identified as a "floodway" on FEMA mapping. Modifications of Floodway areas shall only be permitted if a professional engineering analysis demonstrates to the satisfaction of FEMA that such modifications will not result in detrimental impacts either up or downstream, consistent with FEMA regulations.
- B. Development within Flood Hazard Areas shall not result in and decrease in the flood storage capacity of the flood plain area. Therefore, a subdivision proposed in Flood Hazard Areas shall be accompanied by a grading plan indication how land balancing may be achieved, and how all building sites can be elevated above the base flood elevation for the location and certificate from a professional surveyor shall be presented to FEMA as to where the property will be elevated.
- c. If a subdivision is approved in a Flood Hazard Area, the Subdivider shall be required to post a performance bond guaranteeing execution of the grading plan. The grading plan shall be executed, and the results certified by a professional Engineer or professional surveyor prior to the plat being signed by the Seneca County Engineer and Seneca Conservation District and submitted to the County Recorder. The plat shall be accompanied by restrictive covenants prohibiting the placement of any fill material in areas lying below the base flood elevation, and the Subdivider shall be responsible for enforcement of the covenants until all lots in the subdivision have been conveyed to others.

#### 2. Flood Control and Storm Drainage Facilities:

Flood control or storm drainage facilities shall be provided as follows:

- A. All new subdivision shall be designed in such a manner that the volumetric flow of storm water discharge after development does not exceed the volumetric flow of storm water discharge prior to development. The basis for determining storm water discharges and for designing new storm drainage shall be provided for the SRPC Construction Codes, with checks at twenty-five (25), and one hundred (100) year storms. Detention- retention calculations shall be reviewed by the Seneca County Engineer. All lots within recorded subdivisions shall be graded to provide positive drainage so as to avoid of standing water.
- B. Access to flood control or storm drainage ditches and channels shall be by means of easements. Such easements shall be not less the thirty (30) feet in width, exclusive of the width of the ditch or channel, and an easement of this type shall

be provided on one (1) side of a flood control or storm drainage ditch, channel, or similar type facility.

REPR

MALA

C. Flood control or storm drainage easements containing underground facilities shall have a minimum width of thirty (30) feet with center-line pipe located no closer than ten (10) feet from the side.

24 | Page

# **ARTICLE V- IMPROVEMENTS**

The improvements set forth under this Article are to be considered as the minimum acceptable standard. All improvements for which standards are not specifically set for herein shall have said standards approved Resolutions of the Board of Seneca County Commissioners. All improvements must meet the approval of the Seneca County Engineer.

Prior to the undertaking of any improvements, the Subdivider shall deposit as escrow, with the Board of County Commissioners cash or a certified check, whichever the Subdivider selects, or a surety bond acceptable to the County Commissioners, to ensure faithful completion of all improvements within the time specified. The amount of the deposit shall be 110% based upon an estimate by the Professional Engineer. The Developer 1) pays the full cost of construction, 2) puts up escrow, 3) estimates the project length in days, 4) The Inspector provides the "as built" plans. The County Commissioners shall release the performance escrow as work is completed and approved by the County Engineer.

Prior to the acceptance of improvements by the County, a one (1) year maintenance bond in an amount of 100% of completed projected cost shall be posted by the Subdivider. Improvements shall be provided by the Subdivider in accordance with the standards and requirements established in this Article V and/or any other such standards and requirements which may from time to time be established by Resolution of the Board of County Commissioners.

### **Section 500. STREETS:**

Per plans approved by the Board of Seneca County Commissioners and in accordance with details and specifications. All streets and appurtenances thereto shall be constructed in accordance with Seneca Regional Planning Construction Code or modifications there to on file at the Seneca County Engineers/Commissioners Office.

# Section 501. PUBLIC UTILITIES:

1. Requirements for Underground Wiring: Per plans approved by the Board of Seneca County commissioners and in accordance with details and specifications. The subdivider shall make arrangements for all lines to be constructed as provided in Section 301, 1a-VIII of this document and other similar services distributed by wire or cable to be placed underground entirely throughout a newly subdivided area, except for Major and Secondary Thoroughfare rights-of-way, and such conduits or cables shall be placed within private easements provided to such public utility service e companies by the developer or within dedicated public ways; provided, however, that overhead lines may be permitted within the limits of said newly subdivided area upon approval of the Seneca Regional Planning Commission and Board of Seneca County Commissioners and the Seneca County Engineer at the time of the final plat approval where it is determined that overhead lines with not constitute a detriment to the health, safety, general welfare, plat design and character of the subdivision. All such facilities placed in dedicated public ways shall be planned so as not to conflict with other underground utilities. All such facilities shall be constructed in accordance with National Bureau of Standards Handbook 81 (national Electrical Safety Code). All drainage and underground utility instillations, which traverse privately, owned property shall be protected by easements granted by the subdivider.

2. **Storm Drainage System and Other Drainage Improvements:** Per plans approved by the Board of Seneca County Commissioners in accordance with details and specifications of the U.S. and/or Ohio EPA, National Pollution Discharge Elimination Systems (NPDES), and any other

applicable regulations from the Seneca Regional Planning Construction Code. Said improvements will be assessed 20% of said work to be established as a base for a permanent group under section 6131 of the Ohio Revised Code.

3. Water Supply and or Sewage Disposal- Water Distribution System: Per plans approved by the Board of Seneca County Commissioners in accordance with details and specifications of the Seneca County General Health District, and/or the Ohio Environmental Protection Agency. Regarding single family dwellings.

### Section 502. OTHER IMPROVEMENTS:

**1. Sidewalks:** If sidewalks are proposed, they shall be made of concrete four (4) feet wide, (4) inches thick, and across drives six (6) inches thick, and located one (1) foot from the property line within the right of way. Sidewalks shall be provided on the sides of all road right-of-way adjacent to the subdivision being developed.

**2. Public Walkways/Bikeways (outside of road rights-of-way):** Walkways shall be at least eight (8) feet in width. Planting pockets may be provided in public walkways for tree and shrub planting. No trees with mature height exceeding 12' are permitted. Fences and other improvements may also be required if the Board determines they are necessary to protect the adjacent property owners.

**3. Street Signs:** Street name signs shall be placed at all street intersections and shall conform with current Seneca County Engineer Standards. Traffic regulations signs, in accordance with OMUTCD, will be located as required by the Seneca County Engineer. All signage cost shall be included with development of land. The County Engineer will provide and install the signs the Developer has paid for.

# ARTICLE VI – JURISDICTION

These Regulations shall be applicable to all subdivisions of land within the unincorporated areas of Seneca County as provided in the Ohio Revised Code and any amendments thereto. The Seneca Regional Planning Commission shall have the power of final approval of plats.

The approvals required under the provisions of the Regulations shall be obtained prior to the installation of any subdivision or project improvements within Seneca County in public streets, public alleys, public right-of-way, public reservations, or public easements, or under the ultimate jurisdiction of the County, and shall comply with all the provisions and requirements of this or any other related resolution.

MALA

# ARTICLE VII- INTERPRETATION/MINIMUM REQUIREMENTS

The provisions of these Regulations shall be held to be the minimum requirements adopted for the promotion and preservation of public health, safety and general welfare, and to improve, protect, and preserve the environment of Seneca County. These Regulations are not intended to repeal, abrogate, annul or in any manner interfere with existing regulations or laws of the County, nor conflict with any laws of the State of Ohio, except that unless otherwise noted herein these Regulations shall prevail in cases where these Regulations impose a greater restriction that is provided by existing laws or regulations.

K

- MAN

# ARTICLE VIII – VIOLATIONS AND PENALTIES

The following penalties shall apply to the violations of these Regulations:

AAL AN

1. Whoever violates any rule or regulation adopted by the Board of Seneca County Commissioners for the purpose of setting standards and requiring and securing the construction of improvements within a subdivision or fails to comply with any order pursuant thereto is creating a public nuisance and the creation thereof may be enjoined and maintenance thereof may be abated by action at suit of the County of any citizen thereof. Whoever violates these Regulations shall pay not less than one hundred (100) dollars not more than one thousand (1,000) dollars. Such sum may be recovered with costs in a civil action in the Court of Common Pleas of Seneca County. Each day that a violation is permitted to exist shall constitute a separate violation.

2. Whoever, being the owner or agent of the owner of any land within the jurisdiction of these Regulations, transfers any lot, parcel or tract of such land from or in accordance with a plat of subdivision before such plat has been recorded in the Office of the County Recorder, shall forfeit and pay the sum of not less than one hundred (100) dollars not more than five hundred (500) dollars for each lot, parcel, or tract of land sold. The description of such lot, parcel, or tract by metes and bounds in the deed or transfer shall not serve to exempt the seller from the forfeiture provided in this section.

### ARTICLE IX – SEVERABILITY

If any section, paragraph, clause, phrase, or part of these Subdivision Regulations is for any reason held invalid by any court of competent jurisdiction, such decision shall not affect the validity of the remaining provisions of these Regulations; and the application of those remaining valid provisions to any person or circumstances shall not be affected thereby.

Storeth

### **ARTICLE X – REPEAL & AMENDMENTS**

All Resolutions and amendments thereto enacted or adopted by the Board of County Commissioner inconsistent with the provisions of these Regulations and their amendments do not affect or impair any act don't, offense committed or right accruing, acquired or acquired or liability, penalty, forfeiture, or punishment incurred prior to the time enforced, prosecuted, or inflicted.

<

MAL

OR PLUR

### ARTICALE XI – VARIANCE

The following regulations shall govern the granting of variances:

MAL

1. Any variance request must be made to the Seneca Regional Planning Commission in writing ten (10) days prior to the Seneca Regional Planning Commission Meeting.

2. Where the Seneca Regional Planning Commission finds that undue and unnecessary hardship may result from strict compliance with these Regulations, it may grant a variance as defined in ARTICLE II of these Regulations. Such variations shall not have the effect of nullifying the intent and purpose of these Regulations, the Comprehensive Plan, or shall not ament or change any zoning regulations, as they exist.

3. In granting variances or modifications, the Regional Planning Commission may require such conditions as will, in its judgement, secure substantially the objective of the standards or requirements so varied or modified. All such variances must be issued in writing.

### ARTICLE XII – APPEAL

Any person who believes he has been aggrieved by these Regulations or the action of the Seneca Regional Planning Commission has the rights of appeal as set forth in Chapter 711 of the Ohio Revised Code or any applicable Section of the Ohio Revised Code.

KOR-PERRO

# ARTICLE XIII – LARGE LOT DEVELOPMENTS

### **SECTION 1300.** Large Lot Development Rules.

**1300.01 General.** The purpose of this Section 1300 is to establish the procedure for review and approval of large lot divisions as authorized under Section 711.113 of the Ohio Revised Code.

The Large Lot Development Rules shall be used to request a proposed division of a parcel of land along an existing public street, not involving the opening, widening or extension of any street or road, and involving the establishment of any lot ranging in size from not less than 5.01 acres to no more than twenty (20) acres. A proposed division of land under and incompliance with this Section 1300 shall not be considered a subdivision for purposes of division (B)(1) of Section 711.001 of the Revised Code and Need only be approved under the provisions of the Section 1300.

A large lot Development (LLD) application (see Attachment C) shall be filed by the landowner or designated representative at the Seneca Regional Planning Commission office. In addition to the submittal requirements set for below, the application shall include two copies of the survey drawing and one copy of the legal description, the signed and completed application form and the required fee.

#### 1300.02 Pre-Application Conference and Sketch Plan.

Prior to filing a formal LLD application, an applicant is encouraged to request and informal discussion with RPC staff to discuss the procedure for approval and to familiarize the applicant with applicable requirements. A request for a pre-application conference shall require the submission of a sketch plan no smaller thank 11" x 17". The sketch plan shall be drawn to a convenient scale of not more than one hundred (100) feet to an inch and shall show the following information:

- A. Location or Vicinity Map.
- B. Ownership of property.
- C. Existing and proposed public roads and easements.
- D. Existing structures.

North arrow.

Outline of areas to be divided.

- G. Approximation of proposed lot lines and dimension.
- H. Important natural features and drainage ways.

I. Information concerning any existing or proposed locations of storm drainage, maintenance ditches and titles, sewage treatment, water supple, and other facilities that impact development.

Within a reasonable period of time following submittal of the sketch plan, RPC staff will meet with the applicant to discuss the proposed division. Staff may request a site visit prior to such discussion, in which case, the applicant shall accompany staff on the site visit. Within two (2) weeks following the site visit (or, if none, following the conference with the applicant), staff shall provide written comments to the applicant on the proposed division.

**1300.03 Survey Requirement.** No division of land involving a metes and bounds description shall be approved or exempted unless it is accompanied by a survey and legal description certified by a Professional Surveyor licensed in the State of Ohio. The survey must meet the County Conveyance Standards, Administrative Code 4733-37, and the County Engineer or designee must approve the survey and description.

**1300.04 Lot Frontage Requirement.** Unless the applicable zoning regulations specifically provide otherwise, all lots created under this Section 1300 shall have a minimum called for in 402-1(i), one hundred twenty-five (125) feet of continuous frontage (measured horizontally) on an existing and improved public/private road measured at the right-of-way line.

**1300.05 Lot Width to Depth Ratio.** Unless the applicable zoning regulations specifically provide otherwise, the maximum depth of a lot measured at the building setback line shall not exceed four (4) times the width of the lot (measured horizontally). For purposes of determining these lot measurements, the lot shall be measured as follows:

- A. A. Depth of all lot shall be considered to be the distance between the mid-points of straight lines connecting to the foremost points of the side lot lines at the front yard setback and the rearmost points of the side lot lines in the rear.
- B. B. Width of a lot shall be considered to be the distance between straight lines connecting front and rear lot lines at each side of the lot, measured at the front building setback line as established by the applicable zoning regulations or, where no zoning exists, 30 feet back from the edge of the current or proposed road right-of-way.

**1300.06** Application Submittal Requirements. An LLD application shall include the following information and materials:

- A. Existing or proposed buildings, well, home sewerage treatment system locations, and design and system replacement area.
- B. Deed wording addressing lot development, conditions or restrictions.

- C. New or additional roadway easements and/or utility easements. Roadway easements must be conveyed and recorded by a separate instrument prior to the recording of the LLD deed.
- D. Appropriate floodplain status information showing areas within the 100-year floodplain/floodway.
- E. Access points in accordance with the agency responsible for the maintenance of the right-of-way for driveway approval.
- F. Drainage improvements in compliance with applicable County standards.
- G. Approval of the LLD from health and zoning authorities.
- H. Approval of the LLD from the County Sewer District if the LLD is proposed to be serviced by public water and/or sewer.
- I. Approval of the County Engineer concerning survey and legal description in conformance with the conveyance standards.
- J. Approval of the Seneca Conservation District regarding existing surface or subsurface drainage.
- K. Approval of the appropriate zoning inspectors, if applicable.
- L. A proposed land division vicinity map.
- M. An approved survey and legal description prepared by a professional surveyor registered in Ohio.
- N. A Location Map certified by a Professional Surveyor. The Location Map may be combined with the survey or may be a separate drawing. The Location Map must include the following:
  - 1. All newly created lot lines for app proposed lot(s).
  - 2. All adjoining public roads.
  - 3. All existing above ground structures (including overhangs) Located within one hundred (100) feet of a newly created lot line.
  - 4. All proposed points of access.
  - 5. The dimensions of the newly created lot(s) and acreage.
  - 6. Signature, Seal and Date.
- O. All applicable Fees
- P. Any other material or information the Regional Planning Commission finds necessary for the review of the large lot development.

In addition, all corners of the proposed lots shall be marked with stakes and colored flagging prior to or at the time of filing the LLD application.

**1300.07 Review and Approval.** If the Commission, acting through the Executive Director of the Executive Director's designee(s), finds that the proposed division is not contrary to any applicable zoning, health, sanitary, flood or access management regulations, existing surface, or subsurface drainage, including, but not limited to, rules governing household sewage

disposal systems or the regulations set forth in this Section 1300, it shall be approved in accordance with the following schedule:

A. For proposed divisions into not more than six (6) separate parcels, approval shall be within seven (7) calendar days after its submission.

B. For proposed divisions into more than six (6) separate parcels but less thank fifteen (15) parcels, approval shall be within fourteen (14) calendar days after its submission.

C. For proposed divisions into more than fifteen (15) parcels, approval shall be within twenty-one (21) calendar days after its submission.

The burden is upon the applicant to demonstrate compliance with these Regulations. Incomplete or deficient applications will not fall under the timetable above. Applicant shall be notified in writing of issues and reason for deficiencies. Upon presentation of an approved application for said parcel, the conveyance shall be stamped "approved by Seneca Regional Planning Commission; No Plat Required under O.R.C. 711.133," and signed and dated by the Executive Director or his designated representative. LLD deeds shall be recorded within 12 months from the date of approval, or the approval expires. Upon the expiration of the approval, any proposed division of the subject tract shall be filed and processed as a new application under Section 1300.

**1300.08 Agricultural and Personal Recreational Purposes Exemption.** A proposed division of a parcel of land long and existing public street, not involving the opening, widening or existing of any street or road, and which meets the acreage requirements set forth in Section 1300.01 but which is to be used only for agricultural or personal recreational purposes (as hereinafter defined) shall be exempt from the LLD approval requirements. Access may be reduced to 35' for Agriculture/Recreation use. Upon presentation of a conveyance of such a parcel, the conveyance shall be stamped "Approved by Seneca Regional Planning Commission; No Approval or Plat Required under O.R.C. 711.133; FOR AGRICULTURAL AND PERSONAL RECREATIONAL USE ONLY," and signed and dated by the Executive Director of their designated representative. If approval has been given the exemption must be recorded on the bottom of the deed.

Nothing in this Section 1300 shall be construed as excluding parcels that are exempt under this procedure that are currently being used only for agricultural or personal recreation purposes from the provisions of these Regulations for any future division or partitions of those parcels.

When parcels that are exempt from the approval requirements under this Section 1300.08 are subsequently to be used for other than agricultural or personal recreational purposes, the Executive Director or their designated representative shall first determine that such a parcel complies with the regulations set forth in Section 1300.

An exemption under this Section 1300.08 shall require a statement (see Attachment E) signed by the grantor and grantee, that certifies that the proposed parcel will only be used for agricultural or personal recreational purposes, and that any subsequent change in use shall require that the Executive Director first determine that the parcel complies with the then current provisions of Section 1300.

For purposes of Section 1300.08 the terms "agricultural purposes" and "personal recreational purposes" shall be defined as follows:

MAL


- Agricultural Purposes-a parcel or parcels that are devoted exclusively to commercial animal or poultry husbandry, aquaculture, apiculture, the production for a commercial use of field crops, tobacco, fruits, vegetables, nursery stock, ornamental trees, sod, or flowers or other similar agricultural uses.
- **Personal Recreational Purposes**-a parcel or parcels that are devoted exclusively to personal recreational use of a private type and nature that is conducted by the owner(s) of such parcel(s) or the individual(s) entitled to exclusive use and possession of such parcel(s), without fee or consideration of any kind, excluding and commercial or membership recreational type of use whether or not for fee or profit.

# ARTICLE XIV – ENACTMENT

# **Section 1400. EFFECTIVE DATE**

These Regulations shall become effective from and after the date of its approval and adoption by the Seneca Regional Planning commission and Board of Seneca County Commissioners after Public Hearing and certification to the Seneca County Recorder.

Anthony Paradiso, President Seneca Regional Planning Commission	Date
Mr. Anthony Paradiso, Seneca County Commissioner	Date
Mr. Tyler Shuff, Seneca County Commissioner	Date
Mr. Michael Kerschner, Seneca County Commissioner	Date
RAT	



## ATTACHMENT A PRELIMINARY PLAT APPLICATION SENECA REGIONAL PLANNING COMMISSION SENECA COUNTY, OHIO

	SERE		, onio		
Subdivision Name:					
Township:	_ Section:		Existing Roa	d:	
Name and Address of Property	owner:				
					-
				$\sim$	-
Owner Phone Number:		Owner Em	ail:	$\sim$	
Surveyor:		Surveyor (	Contact Name:	0	
Surveyor Phone Number:		Surveyor E	mail:		
Is this a NEW Subdivision		_YES		NO	
Is this an UPDATE to and exis	ting Subdivision	YES	<b>~</b>	NO	
FEE STRUCTURE:		4			
*PLAN APPROVELS		$\overline{0}$		\$200.00	]
*ADMINISTRATION FEE				\$250.00	
*APPLICATION FEE (UP TO 2 H	OURS OF REVIEW)	$\mathbf{i}$		\$300.00	_
APPLICATION FEE (BEYOND 2 H	OURS OF REVIEW)			\$150.00 PER	
	7			HOUR	
**APPLICANTS WILL BE RESPO	NSIBLE FOR ALL ADVI	ERTISING FEES A	ND WILL BE INVC		(
*THE PLAN APPROVAL, ADMIN	ISTRATION AND INTI	TIAL APPLICATIO	ON FEE SHALL BE F	PAID AT TIME OF SU	BMIS

All checks are be made payable to Seneca Regional Planning Commission and Submitted with the initial application.

The following items shall e included on, ow with the Plat for consideration by the Regional Planning Commission:

FINAN

## ATTACHMENT A PRELIMINARY PLAT APPLICATION SENECA REGIONAL PLANNING COMMISSION SENECA COUNTY, OHIO

#### **Existing Conditions:**

 Sı	ıł	)(	liv	/is	i	01	n		
т			1	Б				•	

- \_\_\_\_Legal Description
- \_\_\_\_Name & Address of Engineer/Surveyor/Planner
- \_\_\_\_North Arrow
- \_\_\_\_Plat Scale (1"-200' Minimum)
- \_\_\_\_Vicinity Map (1"=1000' Minimum)
- \_\_\_\_Boundary with Dimensions
- Existing Easements on proposed Plat and adjoining property
- \_\_\_\_\_Names of adjoining Subdivisions and Parcel Owners
- Banes if adjoining Streets and Right-of-way widths, Railroads, and other utilities or easements
- \_\_\_\_Location of existing water mains, sanitary and storm sewers
- Existing topography (2 foot intervals- U.S.G.S. Datum)
- \_\_\_\_Flood Hazard Boundary (when applicable)
- \_\_\_\_Location of existing buildings, wood, tree lines, creeks & ditches, etc
- \_\_\_\_\_Ditch maintenance special assessments

#### **Proposed Conditions:**

- Location, right-of-ways and names of all proposed streets
- \_\_\_\_Easement location
- \_\_\_\_\_ Public walkways
- \_\_\_\_\_ Lot layout, with approximate Lot dimensions and Lot numbers
- \_\_\_\_Setback Lines
- Lot or parcel use, Number of dwelling units
- Land set aside for Public use
- \_\_\_\_Sanitary Sewer size & location
- \_\_\_\_\_Water Main size & location
- \_\_\_\_Storm Sewer size & location
- \_\_\_\_Detention or Retention areas
- \_\_\_\_Phasing of development
- \_\_\_\_\_Typical Pavement section
- Protective Covenants

Two (2) copies of the Preliminary Plan and the application showing all the required Existing Conditions and Proposed Conditions must be submitted at a minimum of 30 days prior to the regularly scheduled Seneca Regional Planning Commission Board Meeting to be considered for the agenda. It is understood that if all the above requirements are not met the Executive Director may remove this submittal from consideration for the next Board Meeting.

Approval is granted for a maximum of 12 months.

Signature of Owner or Authorized Agent

CTIO'

## ATTACHMENT A PRELIMINARY PLAT APPLICATION SENECA REGIONAL PLANNING COMMISSION SENECA COUNTY, OHIO

FOR PLANNING COMMISSION USE ONLY	
Date Filed:	
Date of Public Hearing:	
Fee:	
Recommendation of Planning Commission: Approval Denial	
Reason for Recommendation:	
Date of Approval:	
Chairman, Planning Commission:	_
EINAL PART NOTE	

## ATTACHMENT B FINAL PLAT APPLICATION SENECA REGIONAL PLANNING COMMISSION SENECA COUNTY, OHIO

Subdivision Name:		
Township:	Section:	Existing Road:
Name and Address o	f Property Owner:	
Owner Phone Numb	er:	_ Owner Email:
Survoyor		Surveyor Contact Name:
Surveyor		
Surveyor Phone Num	nber:	Surveyor Email:
Date Preliminary Pla	t Approved.	
Date Flemminary Fla	1 Approved.	
Requirements for th	he Final Plat Application:	
Complete set of	construction plans	0-
2 Copies of plat	-	
^	ctive covenants	
<b>*</b>	yor seal and signature	
Engineer's estin		
•	d Maintenance Bond	$\sim$
Form letter for s	street dedication completed	$\frown$
Subdivision Nat	_	
Legal Description	on	
Ditch maintenar	nce assessment	
Date, North Arr	ow and Scale	
Name and addre	ess of engineer/Surveyor wh	o prepared the plat
Plat boundaries	with angular and lineal dime	ensions
Bearings and dis	stances to established monut	ments
Monument dese	•	
Locations and N	Names of Existing:	
Street ri	ights-of-waySetbacks	Easements Lot #
	ensionsCurve data	Public land
Base flood elev	ation data	
Phasing of site of	levelopment	
Agency Approv		
		County Sanitary Sewer District
		wnship Zoning Inspector
		neca Conservation DistrictCounty Engineer
	rs signatures of plat dedicati	ion
Surveyor		
Dedication of st	reet and public areas	

## ATTACHMENT B FINAL PLAT APPLICATION SENECA REGIONAL PLANNING COMMISSION SENECA COUNTY, OHIO

This application, copies of the plat showing all items listed above, and one complete set of construction plans shall be submitted a minimum of 10 days prior to the next scheduled Regional Planning Commission meeting to be considered for placement on the agenda. I understand that upon review, if and of the above data has been omitted, the Executive Director shall remove this submittal from consideration for the Regional Planning Commission Agenda.

Certification: the undersigned certifies that the information accompanying this application is true and correct to the best of my knowledge.

			$\sim$	
Signature of Owner or Authorized Agent			Date	
******	******	*****	*****	*****
FOR PLA	NNING CON	MISSION USE	ONLY	
Date Filed:				
Date of Public Hearing:			•	
Recommendation of Planning Commission:	Approval	<u>~</u>	Denial	
Reason for Recommendation:		O		
	X			
Date of Approval:	$Q_{-}$			
Chairman, Planning Commission:				
Secretary, Planning Commission:				
X				

#### ATTACHMENT C MINOR LOT SPLITS/LARGE LOT DEVELOPMENT SPLITS APPLICATION FOR ADMINISTRATIVE APPROVAL Regulated by Ohio Revised Code 711.131, 711.133 & Seneca County Subdivision Regulations Section 303 PLEASE COMPLETE IN PEN OR TYPE

<u>APPLICANT</u>				
PROPERTY OWNER		PHONE		
ADDRESS	CITY	ZIP		
PROPOSED USE:RESIDENTIALCOMMERCIAL	INDUSTRIALAGRICULTURAL/PERSONAL RECREATION	EXEMPTION ATTACHED		
CONTACT PERSON:OWNERAGENT				
IF AGENT, NAME:		PHONE		
ADDRESS	CITY	_ZIP		
EMAIL:		2		
NOTE: PLEASE INCLUDE TW	O COPIES OF THE SURVEY AND ONE COPY OF THE LEGAL SU	JRVEYOR		
<u>SURVEYOR</u>				
PARCEL NUMBER:	TOWNSHIPSECTION	NW NE SW SE		
ROAD NUMBER ROW WIDTH	DRIVE PERMIT APPLIED FOR (DATE)	<b>O</b>		
PARCEL 1 AC PARCEL 2 AC	PARCEL 3 AC PARCEL 4 AC PAR	CEL 5 AC		
IS ANY PART OF THE PARCEL IN A FLOOD ZONEYE	ESNO TYPEAAE PANEL NUMBER			
IS THERE A SPECIAL/DRAINAGE ASSESSMENT ON THE	PROPERTY: _YES _NO			
DISTANCE OF NEAREST DRIVEWAY FROMNORTH	EAST_PROPERTY LINE.,FT ;SOUTHWEST_H	PROPERTY LINE,FT.		
PLEASE GIVE A BRIEF EXPLANATION OF WHAT'S O	CCURRING WITH THIS SPLIT:			
SURVEYOR NAME (PRINT)	SUR	VEYOR NUMBER (PRINT)		
EMAIL:	PHONE: SIGNATURE	· · ·		
.01 – 5.0 ACRES	FEE PAID DATE IN			
5.1 – 20.0 ACRES + 20.0 ACRES	ADDITIONAL TOWNSHIP NON-MEMBER PROCE FEE PAID (\$150.00)	ESSING/ADMINISTRATION		
VARIANCE NEEDED? YES NO TYPE				
DATE VARIANCE APPLIED FOR GRANT				
IF ON STATE ROUTE, WAS ODOT ACCESS GRANTED?		3Y		
PERFORMANCE BOND REQUIRED YE				
AGENCY APPROVALS (IF REQUIRED)				
SENECA COUNTY GENERAL HEALTH DISTRICT (SCC The proposed lot(s) is still subject to Household Sewage Treatm	CHD)	d by the SCGHD does not preclude		
denial of an installation permit pursuant to rule 3701-29-09 of th	e Ohio Administrative Code.			
FLOODPLAIN MANAGER)YESNO	OPMENT OF ANY KIND, INCLUDING FILLING IS PROHIBITED WIT	THIN A FLOODPLAIN		
ZONING INSPECTOR (IF APPLICABLE)       Yes       NO       APPROVED       DENIED       SIGNATURE:         DATE SENT:       DATE RECEIVED:       DATE RECEIVED:       YOU ARE STILL REQUIRED TO SECURE A ZONING PERMIT BEFORE CONSTRUCTION				
SENECA REGIONAL PLANNING COMMISSION APPR APPROVALS WILL EXPI	OVED DENIED SIGNATURE & DATE: IRE IF TRANSFER DOES NOT OCCUR WITHIN 12 M	IONTHS		
PRELIMINARY COMM	ENTS THAT MUST BE ADDRESSED BEFORE APPR	OVAL		
	In order to conduct the review, a completed Site and Soil			
	Dugh its review whether or not the provisions of the Ohio           ASE CONTACT MATT BECKMAN AT 419-447-3691         Ext. 331 IF YOU 1			
Soil and Water				
County Engineer				
Zoning				
Tax Map				
UPDATES:				

#### **INSTRUCTIONS**

#### **APPLICANT:**

To ensure proper consideration of this application the following must be completed.

- 1. All local *township zoning requirements* including minimum road frontage/lot width and minimum lot size must be met. For this information contact the township zoning inspector.
  - 2. All county subdivision regulations concerning minor land divisions must be met.
  - 3. Both the applicant & surveyor's section of the application must be filled out in their entirety.
- 4. *Two (2) <u>copies of the survey</u> (18 X 24 or 24 X 36) and <i>one (1) copy of the <u>legal description</u>* completed by a registered State of Ohio surveyor must accompany each application.
- 5. It is preferred that all fees are paid with a personal check or money order, no credit cards. Fees as of January 1, 2003 are \$40.00 for a minor lot split, \$10.00 thereafter for a 2<sup>nd</sup>, 3<sup>rd</sup>, or 4<sup>th</sup> *from the same tract* after the first
- 6. Fees as of December 5<sup>th</sup>, 2018 An additional processing/administration fee of \$150.00 will be charged for nonmember townships payable by the applicant.
- 7. When completed bring these items to the Seneca Regional Planning Commission (SRPC) located in County Services Building, 71 S. Washington St., Suite 1104 Tiffin, Ohio between 9:00 a.m. and 3:30 p.m. Monday thru Friday.

#### EACH OF THE ABOVE ITEMS MUST BE MET, OTHERWISE THE APPLICATION WILL BE RETURNED TO THE APPLICANT.

#### **SURVEYOR:**

According to the Seneca Regional Planning Commission Subdivision Regulations and the County Conveyance Standards, the following information is required for all surveys accompanying a lot split application.

1. Documentation showing compliance with Ohio Administrative Code, Chapter 3701-29 governing Home Sewage Treatment System, specifically a Site and Soil Evaluation. (See SCGHD comments on reverse side.)

2. Proposed division of land, including dimensions of the entire original tract.

- 3. Owner of parcel and all adjoining parcels.
- 4. Dimension and location of lot lines of proposed lot.
- 5. North orientation arrow.

6. Existing structures, wells, septic systems/leach fields, easements, site disturbances, existing driveways and other hardscapes or proposed hardscapes, public facilities, direction of drainage, bodies of water, including intermittent and perennial streams and rivers.

7. Any adjoining public road, road right-of-way, zoning setbacks, and distance to the nearest driveway or intersection in each direction within 1,000 feet along the road frontage. Driveway distance should be noted on application form.

8. 100-year floodplain boundary and floodway if it exists anywhere in the original tract. The panel number and flood zone should be noted on the application form.

9. All new parcels require adequate access via a drive. Please ensure the drive permit(s) for the parcel(s) have been submitted to the appropriate authorizing public office.

## EACH OF THE ABOVE ITEMS MUST BE MET, OTHERWISE THE APPLICATION WILL BE <u>RETURNED TO THE APPLICANT.</u>

#### AFTER PLANNING APPROVAL:

The following must be completed in order: (Note: there may be additional charges, please contact appropriate office)

- 1. A professional deed must be prepared for the proposed lot.
- 2. Plat must be taken to the Seneca County Auditor's Office, 2<sup>nd</sup> floor of the RTA Building, for the assignment of house number.
- 3. Bring a copy of new deed to the County Engineer's Tax Map Office located on 2<sup>nd</sup> floor of RTA Building (109 S
- Washington St., Tiffin)
- 4. Bring deed(s) to County Auditor's Office, also on 2<sup>nd</sup> floor of RTA Building.
- Bring deed(s) to County Recorder's Office in order to make the proposed lot an official lot. Recorder's Office located on 1<sup>st</sup> floor of RTA Building.

## PLAT MECHANICS: (TAX MAP OFFICE)

RESEARCH ALL ADJOINERS MONUMENTATION COMMENCES AT ESTABLISHED POINT NORTH ARROW WITH BASIS OF REFERENCE TITLE BLOCK DISTANCE AND BEARING ON EACH LINE SURVEYOR INFO ON DRAWING LEGAL CLOCKWISE PAPER SIZE 18X24 OR 24X36 FIVE PARCEL SPLIT RULE

ROAD RECORDS SUBDIVISION PLATS POINT OF BEGINNING ROW ACREAGE WRITTEN AND GRAPHICAL SCALE ORIGINAL ON MYLAR **REMAINDER AC. & FRONTAGE** ACREAGE OF PARCEL LEGEND OR WRITTEN NOTATIONS CONTROL STATIONS DATE ON LEGAL AND PLAT SURVEYOR INFO & SIGNATURE ON LEGAL LEGAL AND PLAT COMPARED MEETS CLOSURE REQUIREMENTS CHECKED WITH MAP ADJOINER INFO AT END (COMBINE?) COMPUTER GENERATED

SHOULD YOU HAVE ANY QUESTIONS COMPLETING THIS FORM, CALL THE SENECA REGIONAL PLANNING COMMISSION AT 419-443-7936

#### ATTACHMENT D

#### PROCEDURES FOR PLACING MINOR SUBDIVISION/LARGE

### LOT DEVELOPMENT (LLD) TILE

#### UNDER SENECA COUNTY DITCH MAINTENANCE

#### **PURPOSE**

The purpose of this policy is to provide a procedure for a landowner or developer of a minor subdivision/LLD to place new tile mains serving home sites into a permanent maintenance program.

#### **SCOPE**

Currently the permanent maintenance of storm sewers and drainage outlets for major subdivisions are regulated through the "construction Code for the Subdivision Regulation of the County of Seneca, Ohio" Tile mains designed to handle the drainage of two or more proposed or current home sites for minor subdivisions (as defined in Section 303 of Subdivision Regulations of the County of Seneca, Ohio) or LLD are addressed by this procedure.

This procedure will also be used for those landowners requesting tile maintenance for multiple home sites on parcel splits of more than five (5) acres.

## **PROCEDURE**

- The current landowner must submit a survey, by a Professional Surveyor registered in the State
  of Ohio, of the proposed minor subdivision/LLD, including lot layout along with the tile
  easement to an approved outlet (i.e., open ditch or other outlet approved by the Seneca
  Conservation District or Board of Health). This survey shall be submitted to the Seneca
  Regional Planning Plat Review Committee or directly to the Seneca County Engineer, Seneca
  Conservation District and Seneca County Board of Health.
- The landowner will meet with a representative of the Seneca Conservation District to discuss the procedure for placing the drainage system on maintenance. The landowner will sign a "Request for Maintenance" (Attachment D1) and provide \$500, to be placed into escrow per the terms on the request.
- 3. The survey shall include a separate tile plan for the proposed tile being placed on maintenance. The tile plan shall be signed by a Professional Engineer in the State of Ohio and include a minimum of the information included on Attachment 2.

Tile plan shall be reviewed by the Seneca County Engineer, Seneca Conservation District and Seneca County Board of Health, within ten (10) working days of receipt of a complete plan by the Seneca Conservation District or Seneca Regional Planning Commission.

- 5. After review by the above agencies and corrections are made, the final tile plan, with the signature of a Professional Engineer, will be submitted to the Seneca Conservation District.
- 6. The Seneca Conservation District will then write the maintenance agreement for the proposed tile within 15 working days of the final tile plan submittal.
- 7. Once the agreement is written, it will be given to the developing landowner (or representative) to be signed by all landowners involved in the project.
- 8. The signed maintenance agreement will be returned to the Seneca Conservation District, and an additional \$300 to start the Maintenance Fund, will be made by the landowner to the Ditch Maintenance Department to establish the permanent fund for the tile... This \$300 transaction amount will not be returned to the landowner and is different than the \$500 Request for Maintenance deposit that is to be held in escrow.
- 9. Once the \$300 start of Maintenance Fund is received, construction can begin on the tile main. It is the developing landowner's responsibility to hire and pay the contractor to install the tile.
- 10. The contractor and/or developer shall meet with the Seneca Conservation District ten (10) days prior to any tile installation. The pre-construction layout of the tile shall be the responsibility of the Professional Engineering firm that designed the tile system. The contractor is responsible for contacting the Seneca Conservation District to view the installed tile <u>before</u> the tile trench is backfilled.
- 11. It is the developing landowner's Professional Engineer's responsibility to certify proper construction and provide "as-built" tile plans showing how the tile was installed versus what was planned. The Seneca Conservation District has the right to inspect tile during and after installation.
- 12. Once the tile and necessary structures are installed and as built tile plans are received from the Professional Engineering firm by the Seneca Conservation District, the \$500 held in escrow will be released back to the developing landowner and the tile plan and maintenance agreement will be recorded by the Seneca County Recorder and placed on to Seneca County Ditch Maintenance13. The landowner and their successor and assigns will be responsible for future tax assessments against property benefits by the maintenance agreement in order to fund necessary maintenance repairs or replacements.

- ANAL-

# **REQUEST FOR MAINTENANCE**

	request assistance from the Seneca 🔦
(Name of person filling out form and making deposit)	~
Conservation District to place the main drainage tile for the	
(Name of Minor Subdivision)	
Minor Subdivision/Large Lot Development in Section numb	
Township of Seneca County, under the S	
Program. I have read and understand the procedures for p	-
maintenance program. I understand that I must put forth \$	
Seneca Conservation District. Once all the procedures for p	
met, the \$500.00 will be returned to me. I further understa	
procedures and/or the tile main is not ready to be enrolled	
within one year of the date I signed this form, that I will for	
the District for the tile project up to the \$500.00. No assist	· ·
maintenance will be completed by the Seneca Conservation the \$500.00 is received.	in District until this form is signed and
Landowner/Developer	Date
Date Funds Received	
Approved by Board of Supervisors	Date
~	

## **TILE PLAN REQUIREMENTS**

The following information is required on all tile plans being proposed for maintenance:

- 1. Title Block
- 2. Location Map
- 3. The location within construction area of all roads, fences, buildings, utilities, bridges, culverts, property lines, and landowners, important to the project
- 4. Benchmarks and Legends (must be set to USGS elevations)
- 5. Watershed Boundary of all parcels benefitting from tile
- 6. Underground utilities notification information- Notice to excavator (OUPS Phone Number 1-800-362-2764)
- 7. Soil types and boundary lines
- 8. Construction approval block
- 9. Plan view of tile layout. (The need for topographic survey and spot elevations of low areas will be determined on a case by case basis.)
- 10. Length, size, quality and kind of tile
- 11. Length, size, and kind of outlet pipe (specify animal guard)
- 12. Stationing and invert elevations at key points (i.e. grade and directional changes etc.)
- 13. Location of all right of way, easements, etc.
- 14. Profile of tile showing ground line and grade
- 15. Minimum trench width and bedding requirements
- 16. Recommended depth, required spacing
- 17. Bill of materials
- 18. Bottom and low flow elevation of outlet ditch
- 19. Hydraulic Design Data

The following information needs to accompany the tile plan before approval:

1. Design calculations which includes parameters or scope of design (i.e. curtain drains, roof downspout, footer drains etc.) Calculation MUST be signed and have the seal of Professional Engineer registered in the State of Ohio.

2.Capacity of tile and the designed grade in cubic feet per second (cfs)

3. Estimated cost of both the materials and installation

4. If tile project is within county or township road rights-of-way then permits shall be obtained and attached to the plan

# ATTACHMENT E

## CERTIFICATION FOR EXEMPTION OF PARCELS TO BE USED ONLY FOR AGRICULTURAL OR PERSONAL RECREATIONAL PURPOSES PURSUANT TO OHIO REVISED CODE SECTION 711.133

The undersigned Grantor(s) and Grantee(s), make the following statements for the express purpose of inducing the Seneca Regional Planning Commission (the "Commission") to exempt from the approval requirement of Section 1300 of the Seneca Subdivision Regulations (the "Regulations") the following described property (the "Property") and to stamp the conveyance of the Property "No Approval Required under O.R.C. 711.133; **FOR AGRICULTURAL AND PERSONAL RECREATIONAL USE ONLY**":

- 1. The Grantor(s) and Grantee(s) certify that the Property proposed for exemption is described as follows:
- The Grantor(s) and Grantee(s) certify that the Property is to and shall be used ONLY for agricultural or personal recreational purposes as defined in Section 1300 of the Regulations.
- 3. The Grantor(s) and Grantee(s) acknowledge and understand that if the Property is subsequently changed in use from agricultural or personal recreational purposes, no such change in use shall be made by the Grantor(s) or Grantee(s) or their successors and assigns unless and until the Executive Director of the Commission or his designated representative first determines that the Property complies with the then current provision of Section 1300 of the Regulations.

The undersigned Grantor(s) and Grantee(s) have signed this Certification on the date(s) set forth below.

GRANTOR(S):	GRANTEE(S):
Name	Name
Date:	Date:
$\sim$	
Name	Name
Date:	Date:
APPROVED BY SENECA REGIONAL PLANNING COM	MISSION DATE:
Approved by Executive Director	